INDEX

SHEET NO.	PLAN REFERENCE NO.	TITLE
		VOLUME 1
1	I1	INDEX
2	VIC1	VICINITY MAP
3-6	SQ1-SQ4	SUMMARY OF QUANTITIES
7-10	RS1-RS4	ROADWAY SECTIONS
11-12	RS5-RS6	SHOULDER DETAILS
13-14	QT1-QT2	QUANTITY TABULATION - SITE PREPARATION
15-30	AL1-AL16	ALIGNMENT/RW/UTILITY PLAN
31-53	PR1-PR23	PROFILES
54-73	SN1-SN20	STRUCTURE NOTES
74-89	DR1-DR16	DRAINAGE PLAN
90-104	DP1-DP15	DRAINAGE PROFILES
105	DD1	DRAINAGE DETAILS
106-113	CG1-CG8	CONTOUR GRADING PLAN
114-117	QT3-QT6	QUANTITY TABULATION
118-136	PM1-PM19	PAVEMENT MARKING PLAN
137-159	PC1-PC23	PCCP DETAILS
160	QT7	QUANTITY TABULATION - NOISE WALL
161-170	W1-W10	NOISE WALL PLAN/PROFILES
171-173	BRIDGE SHEETS 1-3	**NOISE BARRIER WALL DETAILS**
174-176	BRIDGE SHEETS 4-6	**SOLDIER PILE WALL DETAILS**
177-188	BD1-BD12	BARRIER DETAILS
189-205	IL1-IL17	ILLUMINATION PLAN
206-207	IL18-IL19	LUMINAIRE SCHEDULE
208-209	ILD1-ILD2	ILLUMINATION DETAILS
210	CC1	CCTV SYSTEM
211-219	FO1-FO9	FIBER OPTIC DETAILS
220-221	SR1-SR2	SIGN REMOVAL SPECIFICATIONS
222	SL1	SIGN RELOCATION SPECIFICATIONS
223-225	SS1-SS3	SIGN INSTALLATION SPECIFICATIONS

NOTE TO DESIGNER:
FOR ANY CONTRACT THAT CONSISTS OF 30 OR MORE PLAN SHEETS, AN INDEX IS REQUIRED.
THE FEDERAL AID NUMBER IS REQUIRED ON THE FIRST SHEET OF THE PLANS, WHETHER IT IS THE INDEX OR VICINITY MAP.
PLAN REFERENCE NOS. SHALL NOT BE REPEATED.
THE LIMIT ON THE NUMBER OF PLAN SHEETS PER VOLUME IS 225. IN THIS CASE, IT WAS DECIDED TO BREAK THE VOLUMES AT THE END OF THE SIGN SPECIFICATIONS AND THE BEGINNING OF THE SIGNING PLAN.

INDEX (CONTINUED)

SHEET NO.	PLAN REFERENCE NO.	TITLE
		VOLUME 2
226	I2	INDEX VOLUME TWO
227-243	S1-S17	SIGNING PLAN
244-245	SD1-SD2	SIGN DETAILS
246-248	CSD1-CSD3	CANTILEVER SIGN DETAILS
249-250	SBD1-SBD2	SIGN BRIDGE DETAILS
251-253	DRS1-DRS4	DETOUR ROADWAY SECTIONS
254-258	DPR1-DPR4	DETOUR RAMP PROFILES
259	GW1	GEOSYNTHETIC WALL PLAN/PROFILE
260-267	DQT1-DQT8	QUANTITY TABULATION - DETOURS
268	DQ1	DETOUR EARTHWORK/SURFACING/PAVING QUANTITIES
269-303	DS1-1 - DS1-35	DETOUR SEQUENCE 1 PAVING PLAN
304-319	DS2-1 - DS2-16	DETOUR SEQUENCE 2 PAVING PLAN
320-355	DS3-1 - DS3-36	DETOUR SEQUENCE 3 PAVING PLAN
356-376	DS4-1 - DS4-21	DETOUR SEQUENCE 4 PAVING PLAN
377	DMD1	DETOUR MISCELLANEOUS DETAILS
378-379	RSP1-RSP2	RAMP CLOSURE SIGNING PLANS
380-395	CS1-1 - CS1-16	CONSTRUCTION SIGNING DETOUR SEQUENCE 1
	CS2-1 - CS2-16	CONSTRUCTION SIGNING DETOUR SEQUENCE 2
	CS3-1 - CS3-16	CONSTRUCTION SIGNING DETOUR SEQUENCE 3
	CS4-1 - CS4-16	CONSTRUCTION SIGNING DETOUR SEQUENCE 4
	TC1-TC5	TRAFFIC CONTROL PLANS

PLAN REFERENCE NO.
SHEET
OF
SHEETS

NOTE: ALL SHEET REFERENCES, FIRST NOS. OF STRUCTURE CODE DESIGNATIONS AND MATCH LINE SHEET REFERENCES, ETC., THROUGHOUT THE PLANS, REFER TO THE ENTRY IN THE PLAN REFERENCE NUMBER BOX.

FILE NAME	C:\DGN\ExamplePlanSheets\PPM Examples.dgn
TIME	03:08:27 PM
DATE	06/17/2004
PLOTTED BY	OPERATC
DESIGNED BY	DESIGNER
ENTERED BY	CADD OPERATOR
CHECKED BY	TEAM LEADER
PROJ. ENGR.	PROJECT ENGINEER
REGIONAL ADM.	REGIONAL ADM.

THESE LINES MUST BE FILLED IN ON ALL SHEETS WITH THE NAMES OF THE APPROPRIATE PEOPLE

REVISION | DATE | BY

REGION NO.	STATE	FED.AID PROJ.NO.
10	WASH	NH-0000(000)
JOB NUMBER 00Z000		
CONTRACT NO.		LOCATION NO. XL-1234

DATE

P.E. STAMP BOX DATE

Washington State Department of Transportation

EXAMPLE 4-1

INDEX VOLUME ONE

PLOT1

I1

SHEET OF SHEETS