

1 (April 5, 2004)
2 Section 5-04.3(8)A is revised as follows:
3

4 The first paragraph of item 3 subsection C is revised to read:
5

6 The Engineer will furnish the Contractor with a copy of the results of all
7 acceptance testing performed in the field within either 24 hours of sampling or
8 four hours after the beginning of the next paving shift, whichever is later. The
9 Engineer will also provide the Composite Pay Factor (CPF) of the completed
10 sublots after three sublots have been produced. The CPF will be provided by
11 the end of the workday in which the results of the acceptance testing are
12 provided.
13

14 The first sentence in the second paragraph of item 3 subsection C is revised to
15 read:
16

17 Sublot sample test results (gradation, asphalt binder content, VMA and Va)
18 may be challenged by the Contractor.
19

20 The third paragraph of item 3 subsection C is revised to read:
21

22 The results of the challenge sample will be compared to the original results of
23 the acceptance sample test and evaluated according to the following criteria:
24

	Deviation
25 4.75 mm sieve and larger	Percent passing ± 4.0
26 2.36 mm sieve	Percent passing ± 2.0
27 0.075 mm sieve	Percent passing ± 0.4
28 Asphalt binder %	Percent binder content ± 0.3
29 VMA %	Percent VMA ± 1.5
30 Va %	Percent Va ± 0.7

31
32
33 The last sentence of item 3 subsection E is revised to read:
34

35 The calculation of the CPF in a test section with a mix design that did not verify
36 will include gradation, asphalt binder content, VMA and Va.