

1 **SECTION 8-04, CURBS, GUTTERS, AND SPILLWAYS**

2 **April 7, 2003**

3 **8-04.3(1) Cement Concrete Curbs, Gutters, and Spillways**

4 The first paragraph is revised to read:

5

6 Cement concrete curb, curb and gutter, gutter, and spillway shall be constructed with air
7 entrained concrete Class 3000 conforming to the requirement of Section 6-02 except at
8 driveway entrances. Cement concrete curb or curb and gutter along the full width of a
9 driveway entrance shall be constructed with air entrained concrete Class 4000
10 conforming to the requirements of Section 6-02.

11

12 The fourth paragraph is revised to read:

13

14 Expansion joints in the curb or curb and gutter shall be spaced at 15-foot intervals, the
15 beginning and ends of curb returns, drainage structures, bridges, and cold joints with
16 existing curbs and gutters. The expansion joint shall be filled to full cross-section with
17 3/8-inch premolded joint filler. When curb or curb and gutter is placed adjacent to
18 Portland Cement Concrete Pavement, a 1/4-inch thick, 6-inch deep premolded joint filler
19 shall be installed between the two vertical surfaces to prevent cracking. When noted in
20 the Plans, the Contractor shall install the catch basin gutter pan at drainage structures
21 abutting the curb and gutter.

22

23 **8-04.3(1)A Extruded Cement Concrete Curb**

24 In the third paragraph, the second sentence is revised to read:

25

26 The adhesive shall meet the requirements of Section 9-26.1 for Type II epoxy bonding
27 agent.

28

29 **8-04.5 Payment**

30 This section is revised to read:

31

32 Payment will be made in accordance with Section 1-04.1, for each of the following bid
33 items that are included in the proposal:

34

35 "Cement Conc. Traffic Curb and Gutter", per linear foot.

36 "Cement Conc. Traffic Curb", per linear foot.

37 "Mountable Cement Conc. Traffic Curb", per linear foot.

38 "Dual-Faced Cement Conc. Traffic Curb and Gutter", per linear foot.

39 "Dual-Faced Cement Conc. Traffic Curb", per linear foot.

40 "Cement Conc. Pedestrian Curb", per linear foot.

41 "Roundabout Truck Apron Inner Cement Conc. Curb", per linear foot.

42 "Roundabout Truck Apron Outer Cem. Conc. Curb and Gutter", per linear foot.

43 "Extruded Curb", per linear foot.

44 "Cement Conc. Gutter", per linear foot.

45 "Cement Conc. Spillway", per linear foot.

46 "Asphalt Conc. Gutter", per linear foot.

47 "Asphalt Conc. Spillway", per linear foot.

48 "Drain Pipe ____ In. Diam.", per linear foot.

49 "Half Round Plain St. Culv. Pipe ____ In. Th. ____ In. Diam.", per linear foot.

50 "Half Round Tr. 1 St. Culv. Pipe ____ In. Th. ____ In. Diam.", per linear foot.

51 "Half Round Plain Al. Culv. Pipe ____ In. Th. ____ In. Diam.", per linear foot.

1 "Half Round Tr. 1 Al. Culv. Pipe ____ In. Th. ____ In. Diam.", per linear foot.

2 "Hand Placed Riprap", per cubic yard.

3

4 Hand placed riprap will be paid for as provided in Section 8-15.5.

5

6 When catch basin gutter pans are required in the Plans, all costs for providing the
7 widened area of gutter pan shall be included in the curb and gutter bid item.