1 2	SECTION 7-08, GENERAL PIPE INSTALLATION REQUIREMENTS August 4, 2003
3	7-08.3(1)A Trenches
4 5	The first paragraph is revised to read:
6	The length of trench excavation in advance of pipe laying shall be kept to a minimum.
7 8	Excavations shall be either closed up at the end of day or protected per Section 1-07.23(1).
9	
10	7-08.4 Measurement
11	The fifth paragraph is revised to read:
12	
13	Embankment construction before pipe placement under the applicable provisions of
14	Section 7-08.3(1)A will be measured in accordance with Section 2-03.