Watershed Subcommittee Milestones

- April, 2002 conceptual plan / timelines
- July, 2002 first pilot started on SR522
- February, 2003 SR522 results presented
- July, 2003 subcommittee focus shifts second
 Watershed Characterization started on
 I-405
- September, 2003 consultant policy support
- December, 2003 I-405 Watershed Characterization products

Watershed Subcommittee Progress Report

Today – Overview/Status of:

- Screening tooldevelopment/testing
- I-405 North Renton work
- Watershed policy direction

Purpose of Screening Tool

- An internal WSDOT tool to provide transportation project engineers with an early warning that a future project has site-specific conditions that will limit their ability to treat stormwater and mitigate wetland impacts on-site in a cost effective and environmentally sensitive manner.
- Compare Nickel Projects

Benefits


- Fewer surprises
- Improved cost management
- Increased environmental benefits

Methods


- Identify what drives up mitigation costs
- Identify key environmental areas
- Develop automated model
- Evaluate/calibrate model to projects with wetland and stormwater cost data
- Assess tool viability
- Run model on Nickel Project list


Variation in Wetland Costs






Variation in Stormwater Costs







Key Messages

- The screening tool is showing promise
- Still in the development and testing stages
- Results have greatest value when provided early in the planning process
- Results can help direct watershed characterization to projects with greatest cost and resource need
- Project completion expected May 31, 2004


Purpose of Watershed Characterization

- Develop technical methods for watershedbased mitigation of transportation impacts that increase environmental benefits and reduce project cost
- Apply to large projects with complex environmental impacts, early in the planning process


Benefits of Watershed Characterization

- New information to support improved avoidance/minimization of existing resources
- New options for natural resource mitigation and stormwater treatment that mitigate project impacts and provide greater environmental benefit
- Reduced mitigation cost for taxpayers

Mitigation Tools Available



Target mitigation where it's most effective



Target mitigation for maximum benefits

Target landscape- not artificial-storage and treatment



Engineered Flow Control

Example, stormwater detention pond

No benefits beyond water quality/quantity



Restoring Natural Control

Example: wetlands restoration

Many benefits beyond just water quality/quantity

Stormwater Flow Control Focus

- Long-term goal Work to make wetland restoration a stormwater flow control Best Management Practice (BMP) along with vaults and detention ponds
- Project engineers rely on BMPs to treat stormwater (vaults/ponds)
- Substantial potential exists to use natural resource restoration to provide stormwater flow control

Stormwater Flow Control Focus


- We requested and received support from Ecology and WSDOT to explore concept
- Ecology Stormwater Engineer, Foroozan Labib, worked on the technical team to help identify wetland restoration criteria
- Restoration model was successfully tested for sensitivity to quantify wetland flow control

Stormwater Flow Control Focus

- Ecology and WSDOT working through policy implications and technical safeguards
- Once policy/technical issues are resolved, upgrade Ecology and WSDOT stormwater models to quantify flow control potential of wetland restoration sites

I-405
North
Renton
Study
Area







I-405 Project Priorities

- Deliver prioritized list of potential mitigation options
- Refine/Add to watershed methods
- Explore feasibility of treating stormwater flow control by restoring wetlands
- Dispel any inference of a "Black Box"


Establish Spatial Scales for Analysis and Mitigation






Interstate 405, North Renton

Characterize Condition of Study Area




- Water
- Sediment
- Pollutants
- Wood
- Heat
- Aquatic Integrity
- •Upland Integrity

Develop Potential Wetland Restoration Site Database




Develop Potential Riparian Restoration Site Database


Shape	Polygon
ld	ma022
Pot_rip	y
Lu	agr
Cts_rev	3.0
Add_for	У
Mend_for	n
Adi_pl	n
Dau	0



Develop Potential Floodplain Restoration Site Database



Develop Potential Stormwater Retrofit Site Database



Potential Mitigation Needs Lakehurst/Lake Washington


- Stormwater: TIA 45 acres; 23 acre-feet of storage required
- Wetland: Maximum impacts 5.8 acres; estimate of need with ratios 11-17.5 acres
- Riparian: Maximum impacts 2.1 acres; estimate of need 1 acre

Develop Two Priority Site Lists


Key Attributes for Prioritizing Sites

- Environmental benefit
- Proximity upslope of project
- Ecological processes "At Risk"
- Natural resource type (floodplain, wetland)
- Local priority recovery sites
- Sites adjacent to public lands
- Project size

Coal Creek Site Locations



May Creek Site Locations



How are local jurisdictions and other stakeholder groups receiving the Watershed Characterization approach?

How is WSDOT using watershed characterization products and is this information of value?

David Masters

Water Resource Lead
I-405 Environmental Team

Key Messages

- Substantial progress made on methods
- Areas identified for improvement
- Project environmental team using results
- Preliminary restoration modeling completed to quantify wetland flow control potential
- Products are being used and valued

Next Steps

- Work with Ecology on stormwater concepts
- Incorporate wetland restoration model
- Update methods document
- Develop and test project screening tool
- Additional peer review
- Implement methods on new urban project
- Support pilot to institutionalize watershed characterization into state regulatory permitting and project management.

Watershed Characterization Different Perspectives – Similar Results

I-405 N. Renton

Walla Walla

Large urban projects:

- Complex issues
- Large environmental impacts and mit. cost
- Limited potential for on-site mitigation
- Sensitive natural resources

Average project size:

- Comprehensive watershed planning complete
- On-site mitigation cost effective but resource benefits increase offsite