| Project: SR 24 - Yakima Vicinity - I-82 to Keys Road | | | | | |
|--|-----------------|----------|----------|----------|----------|
| Project Length: 1.1 miles, from milepost | 0.0 to milepost | 1.1. | | | |
| | 2000 | 2010 | | 2020 | |
| | | No-Build | Build | No-Build | Build |
| Congested Hours per Day | 0 | 1 | 0 | 5 | 0 |
| AM Peak Period Average Travel Speed | 39 mph | 39 mph * | 39 mph * | 36 mph | 39 mph * |
| PM Peak Period Average Travel Speed | 38 mph | 34 mph | 39 mph * | 30 mph | 37 mph |
| AM Peak Period Average Travel Time | 1.7 | 1.7 | 1.7 | 1.9 | 1.7 |
| PM Peak Period Average Travel Time | 1.8 | 2.0 | 1.7 | 2.4 | 1.8 |
| Daily Delay (vehicle hours per mile) | 16 | 55 | 12 | 152 | 29 |
| * weighted average of posted speeds of 35 and 55 mph within project limits | | | | | |