Capital Cost Estimation Methodology

FSOUNDTRANSIT



General Estimating Methodology

- •Standards
- •Estimate Types
- •Estimate Methods



Standards

•AACE Recommended Practice No. 17R-97

•Probable Construction Cost consistent with Class 4 level of Project Definition

•Construction Specification Institute (CSI) Master Format 2004

•General Format Used for Individual Construction Cost Items

•FTA Standard Cost Categories (SCC)

- •10 Guideway and Track Elements
- •20 Stations, Stops, Terminals, Intermodal
- •30 Support Facilities: Yards, Shops, Administration Buildings
- •40 Sitework and Special Conditions
- •50 Systems
- •60 Right-of-Way
- •70 Vehicles
- •80 Professional Services
- •90 Unallocated Contingency
- •100 Finance Charges



Estimate Types

•Previous ST2 or HCT Study Cost Estimates - Unchanged

•Project Definition Has Not Changed

•Construction Cost Escalated from Base Year to 4th Quarter 2014 using Sound Transit Construction Cost Index (CCI)

•Right-of-Way Cost Escalated from Base Year to 4th Quarter 2014 using Sound Transit ROW Cost Index (ROWI)
 •Allocated Contingency, Professional Services and Unallocated Contingency revised per Current Methodology

•New or Updated System Planning Projects

•Develop Unit Cost Library (UCL) in 4th Quarter 2014 Dollars

•Develop Assemblies (Composite Sections) for Major Construction Elements based on Transit Modes and Alignment Definitions

•Prepare Quantity Takeoffs (QTO), by Assembly, for Identified Projects

•Prepare Cost Estimates for Identified Projects



Estimate Methods

•Unit Cost Library (SCC 10 - 50)

Time & Material Unit Cost

- Labor Uses State of Washington Prevailing Wage Rates, includes Base Wage, Fringe Benefits, Payroll Taxes & Insurance
- Equipment Uses Equipment Rental and Operating Rates published by RS Means
- Material Uses multiple sources including RS Means, ENR Material Reports, Local Vendor Quotes
- Contractors Overhead and Profit Typical markup allowances for contractors home and field office, field in-directs, sales tax, bond, general liability insurance, and profit.

Subcontract Unit Cost


•Items typically procured from a subcontractor - Based on local historical cost data

•Contractor's Markup – Typical markup allowance for general contractors supervision and management


Unit Cost Allowance

•Cost allowance for undefined project elements – Project metric based on historical cost data











	sit	Unit Cost Library Pag System Plan Development (ST3) 7/9/2					
Assembly	Phase	Item	Description	Takeoff Quantity	Bid Unit Price	Total Amount	
10.04.222			PC Seg Box Girder - 2 Track (20' Avg. Pier Ht)				
	03-21-10.60	A010	Reinforcing Steel	112.000 lb	1.74	195.03	
	03-30-53.40	A175	Structural Concrete, In Place, Aerial Pier	0.110 cy	797.27	87.70	
	03-41-36.50	A035	Precast Segmental Box Girder, Double	1.000 lf	4,535.46	4,535.46	
	05-05-23.80	A110	Multirotational Bearing (250 Kip)	0.020 ea	5,112.50	102.25	
	05-73-16.10	A010	Metal Pipe & Cable Railing	1.000 lf	118.12	118.12	
	26-05-26.80	A015	Corrosion Control, Aerial	1.000 lf	5.29	5.29	
	31-63-26.13	A100	Drilled Shaft, 10' Dia.	0.830 vlf	3,650.71	3,030.09	
	33-41-13.60	A025	Trackway Drainage Allowance, Aerial	1.000 lf	76.97	76.97	
	33-71-19.17	A055	Cable Duct, Aerial Guideway	1.000 lf	91.60	91.60	
	03-30-53.40	A195	Structural Concrete, In Place, Track Plinth	0.210 cy	1,115.19	234.19	
	03-30-53.40	A205	Structural Concrete, In Place, OCS Pole Base	0.010 cy	1,373.00	13.73	
	03-30-53.40	A180	Structural Concrete, In Place, Aerial Pier Cap	0.230 cy	1,117.43	257.01	
	32-06-10.10	A100	Site Restoration Allowance	0.640 sy	80.67	51.63	
	05-53-16.50	A010	Service/Safety Walkway	1.000 lf	75.71	75.71	
	26-56-33.10	A010	Walkway lighting, Allowance	1.000 lf	49.40	49.40	
	31-13-13.10	A015	Clearing & Grubbing Allowance, Level 2	3.460 sy	1.12	3.87	
	32-35-16.10	A020	Sound Barriers	4.000 sf	30.90	123.61	
	01-56-23.10	A030	MOT Allowance - Aerial	1.000 lf	69.30	69.30	
			PC Seg Box Girder - 2 Track (20' Avg. Pier Ht)	1.000 RF	9,120,96	9,120.96	



Sound Transit	Unit Cost Library System Plan Development (ST3)										
	Partial Totals										
	Description	Amount	Totals	Hours	Rate		Cost Basis	Percent of Total			
	Labor Material Subcontract	1,335 4,078 35		3 ch				14.63% 44.72% 0.39%			
	Equipment Other	746		2 ch				8.18%			
		6,194	6,194					67.91	67.91%		
	Contractor's Overhead Subcontract Markup Field Supervision	924 4 496			15.000 10.000 8.000	% % %	ccc	10.13% 0.04% 5.43%			
	Home Office Sales Tax - General Sales Tax - Subcontractor	93 458 2			1.500 9.500 4.750	% %	000	1.02% 5.03% 0.02%			
	Bond Gen Libilitv & Builders Risk Profit	62 124 248			1.000 2.000 4.000	% %	ccc	0.68% 1.36% 2.72%			
		2,411	8,605		4.000	70	0	26.43	94.34%		
	Subtotal Construction		8,605						94.34%		
	General Conditions	516 516	9,121		6.000	%	т	5.66% 5.66	100.00%		
	Partial Total		9,121								



Quantity Takeoff (QTO)

		Alternative: SEGMENT:	SP-2 from Segment 7 Segment 9				Everett Station to North Everett 3 Stations: Downtown Everett 19th St
							Everett Community College
	STATIO						Torger Erickson 6/5/2015
	2072+00	2185+00	11,300.00		Chec	ked by	
			2.14	MILES			
SCC	STATIC		DESCRIPTION	COSTID	QTY	UNIT	Comments
Cat	BEGIN	END					
	leway & Track E						
-	10.01 Guideway	: At-grade	At-Grade Ballasted - 1 Track	10.01.001		RF	
			At-Grade Ballasted - 2 Track	10.01.001		RF	All elevated
			At-Grade Embedded Streetcar Track in Asphalt Roadway - 1 Track	10.01.005		RF	
			At-Grade Embedded Streetcar Track in Asphalt Roadway - 2 Track	10.01.006		RF	
_			At-Grade Embedded Streetcar Track in Concrete Roadway - 1 Track	10.01.007		RF	
-			At-Grade Embedded Streetcar Track in Concrete Roadway - 2 Track	10.01.008		RF	
_			At-Grade Direct Fixation Track in Express Median - 2 Track	10.01.009		RF	
-			At-Grade Direct Fixation Track. Exclusive - 2 Track	10.01.010		RF	
			At-Grade Embedded Track, Exclusive - 2 Track	10.01.011		RF	
-			At-Grade Embedded Track, Mixed Traffic - 2 Track	10.01.013		RF	
-			At-Grade Direct Fixation Track, On Existing Structure - 2 Track	10.01.020		RF	
-		-	At-Grade Direct Phation Track, On Existing Structure - 2 Track	10.01.020		RF	
			At-Grade Roadway Track Crossing - 1 Track	10.01.051		RF	
_	10.04 Guideway	A saint Channel		10.01.052		RF	
	10.04 Guideway	Aerial Struct	1	10.04.001		SF	
			Bridge Structure - Modification of Existing Structure			RF	
	2072+00	2082+00	Bridge Structure - 2 Track	10.04.023	4.000	RF	
_			PC Seg Box Girder - 1 Track (20' Avg. Pier Ht)	10.04.122	1,000		
-	2082+00	2087+00	PC Seg Box Girder - 1 Track (30' Avg. Pier Ht)	10.04.123	500	RF	
	2087+00	2122+00	PC Seg Box Girder - 1 Track (40' Avg. Pier Ht)	10.04.124	3,500	RF	
			PC Seg Box Girder - 1 Track (50' Avg. Pier Ht)	10.04.125		RF	
	2122+00	2132+00	PC Seg Box Girder - 2 Track (20' Avg. Pier Ht)	10.04.222	1,000	RF	
			PC Seg Box Girder - 2 Track (30' Avg. Pier Ht)	10.04.223		RF	
	2132+00	2185+00	PC Seg Box Girder - 2 Track (40' Avg. Pier Ht)	10.04.224	5,300	RF	
		-	PC Seg Box Girder - 2 Track (50' Avg. Pier Ht)	10.04.225		RF	
			Twin Sngl PC Seg Box Girder - 2 Track (20' Avg. Pier Ht)	10.04.322		RF	
			Twin Sngl PC Seg Box Girder - 2 Track (30' Avg. Pier Ht)	10.04.323		RF	
			Twin Sngl PC Seg Box Girder - 2 Track (40' Avg. Pier Ht)	10.04.324		RF	
			Twin Sngl PC Seg Box Girder - 2 Track (50' Avg. Pier Ht)	10.04.325		RF	
			PC Seg Box Girder, Long Span - 2 Track (20' Avg. Pier Ht)	10.04.422		RF	



Prepare Cost Estimate

			SOUND TR SYSTEM PLAN DEVE		973)				
			N-01		313)				
RANSIT	ODE: LRT								
CAT			COST			UNIT	BASE	ALLCTD	TOTAL
NO.	DES	CRIPTION	ID	QTY	UNIT	COST	COST	CONTGY	COST
		_							
	DEWAY & TRACK ELEMENT deway: At-grade (All Types)	5							
10.01 Gui	deway: At-grade (All Types) N/A								
		gory Total		0	RF		\$0		\$(
	deway: Aerial structure PC Seg Box Girder - 1 Track	(20) Avg. Dier Ht	10.04.122	1.000	RF	\$7,144	\$7.143.770	30%	\$9,286.90
	PC Seg Box Girder - 1 Track PC Seg Box Girder - 1 Track		10.04.122	1,000	RF	\$7,144 \$7,350	\$3,674,810	30%	\$9,286,90
	PC Seg Box Girder - 1 Track		10.04.123	3,500	RF	\$7,350	\$26,123,895	30%	\$33,961,064
	PC Seg Box Girder - 2 Track		10.04.222	1,000	RE	\$9,121	\$9,121,000	30%	\$11,857,30
	PC Seg Box Girder - 2 Track		10.04.224	5,300	RF	\$9,423	\$49,942,483	30%	\$64,925,221
		gory Total	10.04.224	11.300	RF	40,420	\$96,005,958	30%	\$124,807,74
	N/A Cate	gory Total		0	RF		\$0		\$
10.06 Gui	deway: Underground cut & cov	er							
	N/A								
	Cate	gory Total		0	RF		\$0		\$0
	deway: Underground tunnel								
10.07 Gui	n/A								
	Cate	gory Total		0	RF		\$0		\$0
10.08 Gui	deway: Retained cut or fill N/A								
		gory Total		0	RF		\$0		\$0
10.09 Tra	ck: Direct fixation								
	Direct Fixation Track - 2 Track		10.09.120	11,300	RF	\$1,034	\$11,679,002	30%	\$15,182,703
	Cate	gory Total		11,300	RF		\$11,679,002		\$15,182,703

N-01 Est_06-19-15

7/9/2015



Right –of-Way (SCC 60)

- •Assessed Property Values from County Assessor
- •Real Estate Adjustment Factors for typical difference between assessed value and sale value for residential & commercial property by location

•Profile Factors – adjustment for:

Aerial = 0.75
At-Grade = 1.00
Deep Tunnel (>70 ft) = 0.50

■Shallow Tunnel (<70 ft) = 0.65

•ROW Contingency – 1.65

•Range - <u>+</u> 15%



Vehicles (SCC 70)

•Cost for vehicles will be included based on recent procurement contracts by Sound Transit.



Professional Services (SCC 80)

Projects under \$25M	Allowance	Projects over \$25M	Allowar
Admin *	7.00%	Admin *	6.00%
Prelim. Engineering	9.50%	Prelim. Engineering	5.00%
Final Design/ DSDC	15.50%	Final Design/ DSDC	10.00%
Third Parties	2.00%	Third Parties	2.00%
Const. Management	14.00%	Const. Management	9.00%
Total **	48.00%	Total **	32.00%

*Admin is a percent of SCC 10-70 plus all other soft costs. All others are percent of construction.

**Actual effective total is greater than shown due to the application of Admin to nonconstruction costs.



Contingencies

•Allocated Contingency – Applied by SCC category to line items within Cost Estimate

•SCC 10 – 50: 30% Contingency

•SCC 60: 65% Contingency

•SCC 70: 20% Contingency

•SCC 80: Calculated on total values that include design allowance, art allowance and change order contingency

•1% for Art Allowance – Applied to Subtotal of SCC 10 – 50

•Change Order Contingency – Applied to Subtotal of SCC 10 – 50 including Allocated Contingency

•Unallocated Contingency – Applied to Subtotal of SCC 10 – 50, including Art Allowance and Change Order Contingency



